

Back Stop for Harlowton Baseball

2 7/8" X 15' DQ-40 PIPE POST

1 5/8" X 10'6" DQ-40 PIPE POST

Backstop Adapters

120" 9 GA. GBW (2" Mesh) KK CHAIN LINK FABRIC

72" 11 GA. GBW (2" Mesh) KK CHAIN LINK FABRIC

118" 3/16" X 3/4" TENSION BAR

70" 3/16" X 3/4" TENSION BAR

2 7/8" REGULAR TENSION BAND

2 7/8" REGULAR BRACE BAND

1 5/8" PRESSED STEEL RAIL-END

5/16" X 1 1/4" CARRIAGE BOLT

6 1/2" 9 GA. ALUMINUM TIE WIRE

1 7/8" X 6' DQ-40 PIPE POST

1 7/8" PRESSED STEEL CAP

TOTAL AMOUNT DUE: \$ 1900.00 this is for one part of the back stop you will need
3 of them total so $1900.00 \times 3 = \$5700.00$ for the entire back stop plus gates

GATES

One on City field, 2 on county

12 ft gate \$350.00

4 ft gate \$200.00 x 3 =\$600.00

Labor cost \$3000.00

Miscellaneous post and chain link will be an additional cost

Estimate Total: \$3,950 (w/o miscellaneous)

Total Project Estimate: 9,650

Budgeting for \$12,000